ENGINEERING DEPARTMENT.

LOWER CHANNELS DIVISION, MYSORE.

Notification dated 9th October 1925.

A sum of Rs. 4-7-7 is due to the contractor Agraharam Malla Subbudu for work done in Left Bank Low Level Canal. If this is not claimed within three months from the date of thi notification either by the party or his legal heirs, the same will be credited to Government

R. THIPPAIYA,
Executive Engineer.

CHITALDRUG DIVISION.

FORM OF ADVERTISEMENT.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 16th November 1925, forthe construction of a Maternity Hospital with wards and out-houses at Davanagere, Chitaldrug District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1927.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M., and 5 P.M., on office days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 750 in cash or Government Promissory Notes as earnest money and be superscribed Tender for construction of a Maternity Hospital with Wards and Out-houses at Davangere Chitaldrug District.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for constructing a Maternity Hospital at Davangere, Chitaldrug District.

Serial No.	Items of work.	Unit	Quantity of work
1	Earthwork excavation and filling in basement	100 C.ft.	116·98
2	Stone jelly concrete in chunam	"	24·29
3	Trapstone or burnt stone in chunam	"	104·07
4	Burnt brick in chunam	"	102·40
5	Archwork with burnt brick in chunam	C.ft.	284
6	Teakwood glazed doors ¼ and ¾ panelled shutters with ventilators glazed top with fittings, iron clamps, etc., complete	S.ft.	574
7	Teakwood panelled doors with fixtures complete	"	46
8	Do battoned doors complete	"	93
9	Do window half glazed and half panelled or lowered in four halves iron clamps, etc., complete	"	525
10	Do windows with panelled shutters outside and glazed shutters inside with iron bars complete	"	47
11	Do battoned windows complete	"	81
12	Do ventilators glazed with fixed shutters, or movable shutters with iron bars, etc, complete	"	201
13	Do circular ventilators	"	42
14	L. I. ventilators with expanded metal complete	"	69
15	Teakwood cupboards, glazed shutters, planking, etc., complete	"	108
16	Burnt stone slabs 6" thick dressed for retaining walls and lintels for doors, etc.	Ft.	1,304
17	Rolled steel beams including Railway freight and hoisting, painting, etc., complete	Cwt.	47½
18	Iron truss complete including painting, hoisting, etc., complete	No.	1
19	Teakwood work wrought and put up with oiling, etc.	C.ft.	476·53
20	Terrace brick on edge 9" thick with plastering, etc.,	Sqr	31 89
21	Roofing with 1st class Mangalore tiles, teak reepers, etc.,	"	26·19
22	Ridge tiles set in mortar	R.ft.	78
23	Plastering with chunam	Sqr.	206·25
24	White and colour washing	"	206·25
25	Flooring with Henkey's 9" square tiles over 3" concrete and cement pointing	"	38·10
26	Flooring with Italian tiles Herogonal on 3" concrete and dado tiles for walls 2½' high pointed	"	5·39
27	Flooring with Cuddapah slabs 1½" to 2" thick over 3" concrete bed and cement pointing complete	"	7·48
28	Parapet wall 18" high and 9" thick with ornamentation	R.ft.	514
29	Do as per design between passage front	"	16
30	Do wall 1½' thick and 2' height	"	65
31	Gable ornamentation wall over	"	52
32	Cornice 9" thick	"	530
33	Do 1½' thick	"	111
34	Moulding central gable with frieze work	"	48
35	Teakwood eave board ornamental 8" x 1"	"	169
36	Painting doors and windows with silicate paint (chocolate)	Sqr.	32·75
37	Wood oiling to doors and windows	"	3·95
38	Teakwood terminals pendents small	No.	4
39	Masonry final ornamentation in gable	"	2
40	Do small do	"	6
41	Do vases do	"	12
42	Masonry finial (ornamental)	"	2
43	Ornamental work in front of doors	"	1
44	Gable ornamentation scrolls, etc.,	"	1
45	Inscription	L. S.	..
46	Teakwood sun shades with Mangalore tiles eave board etc., complete	R.ft	86
47	Do pillars with base and caps, etc., complete	No	14
48	Brackets with teak work	"	30
49	Ornamental sun shades	"	2
50	Balastrading in front of openings	"	8
51	Cast iron down water pipes in rear	"	12
52	Water spouts	R.ft.	60
53	Masonry dwarf wall over roof 9" x 9"	"	40
54	Providing Hindustani pattern latrine with necessary partition walls 7' with doors in latrine block	No.	5
55	Constructing plinth drain all round with sinks behind latrine	L. S.	..
56	Providing sinks complete with pipes	No.	4
57	Providing pestle and mortar	"	4
58	Pointing with cement	Sqr.	10·28
59	Chunam pointing to basement	"	2·70
60	Providing and fixing cast iron pipe 9" diameter for chimneys	No.	4
61	Dismantling wall or scraping for terracing joint, etc., to the old wall	L. S.	..
62	Clearing site and levelling ground	"	..
63	Unforeseen charges such as side parapets and of steps, etc., ornamental works	"	..
64	Compound wall 4½" thick x 3' high with 9" cube base including foundation, basement coping and plastering, etc., with ¾ pilasters at equal intervalscomplete	R.ft.	1,000

A. TANDONI RAO,
Executive Engineer.